



ENGINEERING SERVICES DEPARTMENT
2220 MAGNOLIA STREET
CERES, CA 95307
(209) 538-5792
FAX (209) 538-5759

CITY COUNCIL
CHRIS VIERRA, MAYOR
KEN LANE, BRETT DUROSSETTE
LINDA RYNO, MIKE KLINE

Safe Route to School Kinser & Hackett Corridor Project

ADDENDUM NUMBER 4

Date: October 21, 2016

PROJECT: **SRTS Kinser & Hackett Corridor Project
ATPL-5241 (057)**

Addendum Number 4 is being issued to the Notice to Bidders, Specifications and Plans, for the Safe Route to School Kinser & Hackett Corridor Project. Bids for this proposal are to be opened on **Tuesday, October 25, 2016 at 2:00 p.m.**

The following is to be changed:

Disregard Bid Item Description numbering, see description name instead that correlates to Bid Item.

1. **Bid Item Install Elevated Crosswalk** – Payment under this item shall be considered full compensation for all labor, material, tools, equipment and incidentals required to furnish and install complete elevated crosswalks in accordance with the Plans and Specifications. AC for elevated crosswalk will have a maximum gradation of 1/2". Removal and replacement of 2"AC/4"AB shall be paid through Bid Items "remove asphalt placement" and "asphalt placement". Traffic symbols and/or Lettering shall be paid through "add thermoplastic traffic stripping, lettering and symbols". This item will be paid for Per Each elevated crosswalk complete in place at the unit price in the Bid Schedule.

The description above pertains to each unit completed, (1) at Hackett Road (1) on Kinser Road. New Bid Sheet attached.

2. **Minor Concrete (Bulb Out Labor Only)** – Payment under this item shall be considered full compensation for all labor required to construct concrete bulb outs including curb ramps to the lines and grades shown and specified. All materials, tools equipment and incidentals for bulb outs is included in Bid Items "Sidewalk" and "Curb Ramp". This bid item will be paid for Per Location of each Bulb-Out completed at the unit price bid in the Bid Schedule.
3. New Bid Schedule attached, changes made are shaded for your convenience.

IF YOU SUBMIT A BID, A SIGNED COPY OF THIS ADDENDUM MUST BE ATTACHED HERETO.

Sincerely,



Leisser P. Mazariegos
Resident Engineer, Engineering Services Department

Contractor _____

Signature _____

Date _____

BID ITEM LIST
SRTS Kinser Road and Hackett Road Corridor Project
Project # ATPL-5241(057)

Item No.	Item Description	Estimated Quantity	Unit	Unit Price	Total
1	Mobilization	1	LS		
2	Traffic Control	1	LS		
3	Water Pollution Control Plan	1	LS		
	<u>Kinser Road</u>				
4	Clearing & Grubbing	1	LS		
5	Remove Concrete (Sidewalk)	1,915	SF		
6	Remove Curb and Gutter	366	LF		
7	Remove Asphalt Pavement	12,208	SF		
8	Minor Concrete (Sidewalk)	5,447	SF		
9	Minor Concrete (Private Driveway)	807	SF		
10	Minor Concrete (Curb and Gutter)	975	LF		
11	Minor Concrete (Curb Ramp Labor Only)	11	EA		
12	Minor Concrete (Bulb-Out Labor Only)	2	EA		
13	Asphalt Placement (2'AC/4"AB)	14,420	SF		
14	Truncated Domes on Existing Curbs	20	EA		
15	Truncated Domes on New Ramps	10	EA		
16	Remove Existing Traffic Stripping, Lettering, & Symbols	3,141	SF		
17	Add Thermoplastic Traffic Stripping, Lettering, & Symbols	1	LS		
18	Paint Curb	281	LF		
19	12" Class III RCP Storm Drain	40	LF		
20	Pedestrian Railing- Pedestrian Barrier	48	LF		
21	Furnish and Install Signage	1	LS		
22	Furnish and Install Storm Drain Manhole	1	EA		
23	Furnish and Install Catch Basin	2	EA		
24	Solar Powered Advance Flashing Beacon (AFB)	4	EA		
25	School Assembly C (25 MPH) Complete with mounting hardware	4	EA		
26	Solar RRFB SC315 w/Dual Light bars, XAV2E PPB and 4" Top Mount	2	EA		
27	S1-1 (30" X 30") complete with mounting hardware	4	EA		
28	W16-7P (L) (24" X 12") Complete with mounting hardware	2	EA		
29	W16-7P (R) (24" X 12") complete with mounting hardware	2	EA		
30	Type 1B (12 Feet Pole)	5	EA		
31	Type 1B Foundation with Anchor Bolts and cover	5	EA		
32	Replace Existing Fences, Driveways, Gates and Other Appurtenances on Private Property	1	LS		
33	Raise Utility Valves to Final Grade (Water)	8	EA		
34	Raise Sanitary Sewer Manholes to Final Grade	1	EA		
35	Raise Storm water Manholes to Final Grade	1	EA		
36	Install Elevated Crosswalk	1	EA		

<u>Hackett Road</u>				
37	Clearing & Grubbing	1	LS	
38	Remove Concrete (Sidewalk)	775	SF	
39	Remove Curb and Gutter	107	LF	
40	Remove Asphalt Pavement	1,388	SF	
41	Minor Concrete (Sidewalk)	3,403	SF	
42	Minor Concrete (Private Driveway)	1,915	SF	
43	Minor Concrete (Curb and Gutter)	722	LF	
44	Minor Concrete (Curb Ramp Labor Only)	0	EA	
45	Minor Concrete (Bulb-Out Labor Only)	2	EA	
46	Asphalt Placement (2'AC/4"AB)	4,297	SF	
47	Truncated Domes on Existing Curbs	11	EA	
48	Truncated Domes on New Ramps	3	EA	
49	Remove Existing Traffic Stripping, Lettering, & Symbols	2,751	SF	
50	Add Thermoplastic Traffic Stripping, Lettering, & Symbols	1	LS	
51	Paint Curb	301	LF	
52	12" Class III RCP Storm Drain	64	LF	
53	Pedestrian Railing- Pedestrian Barrier	60	LF	
54	Furnish and Install Signage	1	LS	
55	Furnish and Install Storm Drain Manhole	1	EA	
56	Furnish and Install Catch Basin	3	EA	
57	Furnish Signage R9-11- Sidewalk Closed Ahead Cross Here	1	EA	
58	Solar Powered Advance Flashing Beacon (AFB)	4	EA	
59	School Assembly C (25 MPH) Complete with mounting hardware	4	EA	
60	Solar RRFB SC315 w/Dual Light bars, XAV2E PPB and 4" Top Mount	2	EA	
61	S1-1 (30" X 30") complete with mounting hardware	4	EA	
62	W16-7P (L) (24" X 12") Complete with mounting hardware	2	EA	
63	W16-7P (R) (24" X 12") complete with mounting hardware	2	EA	
64	Type 1B (12 Feet Pole)	6	EA	
65	Type 1B Foundation with Anchor Bolts and cover	6	EA	
66	Replace Existing Fences, Driveways, Gates and Other Appurtenances on Private Property	1	LS	
67	Raise Utility Valves to Final Grade (Water)	6	EA	
68	Raise Sanitary Sewer Manholes to Final Grade	1	EA	
69	Raise Storm water Manholes to Final Grade	1	EA	
70	Install Elevated Crosswalk	1	EA	
71	Bid Alternate 1: Remove & Replace AC and Traffic Loops	2,560	SF	

TOTAL BID: _____

NOTE: "TOTAL BID" Is only on the last page of the BID ITEM LIST